BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42420

APPROVED SCHEDULE - B

o.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

lame of Work:Maintenance of Community Property in Ward No.8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
1	134.53	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer. (P. No. 116, I.No. 15.51.2 of SR 2018-19). with Primer	Sqm	85.34	Rupees Eighty Five and Thirty Four Paise Only
2	31.65	aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grovesection 2.683 kg/m and bottom 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick prelaminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m. from floor level; and 5.5mm. thick plain glass for middle portion viz., 0.9m. to 2.13 m. and top panel with lower	Sqm	4546.81	Rupees Four Thousand Five Hundred Forty Six and Eighty One Paise Only
3	5.04	KSRB 15-17.4 : Applying priming coat over new wood surface and / or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.(Page. No. 121 Item No. 15.58 SR 2018-19)	Sqm	47.41	Rupees Forty Seven and Forty One Paise Only
4	5.04	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.(Page. No. 121 Item No. 15.60.1 SR 2018-19)	Sqm	91.98	Rupees Ninety One and Ninety Eight Paise Only
5	1	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locl<ing arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1000 litre capacity) Specification No.KBS 13.22 (P.No.96, I.No.13.78 of PW, P&IWTD S.R 2018-19)	each	6474.58	Rupees Six Thousand Four Hundred Seventy Four and Fifty Eight Paise Only
6	40	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes. (P.No.99, I.No. 13.86.2 of KPWD SR 2018-19)	m	222.84	Rupees Two Hundred Twenty Two and Eighty Four Paise Only

Signature of the contractor

27/07

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender I- SRIKANTH K S (A CONSTRUCTION	
				In Figures	In Wo
7	40	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes(P.No.99, I.No. 13.86.3 of KPWD SR 2018-19)	m	277.83	Rupees Two Hundred Seventy Seven and Eighty Three Paise Only
8	2	KSRB 11-15.3 : Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications. (P.No.84, I.No. 12.41 of KPWD SR 2018-19)	unit	1077.2	Rupees One Thousand Seventy Seven and Twenty Paise Only
9	2	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.No.82 I.No.12.23 of PWDSR 2018-19)	unit	3799.6	Rupees Three Thousand Seven Hundred Ninety Nine and Sixty Paise Only
10	17.55	KSRRB M800-7. Painting:-Providing and applying two coats of ready-mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.MORTH Specification No. 803 Painting on Steel Surface(P.No.181, I.No24.8.1 of PW,P&IWTD S.R 2018-19))	Sqm	68.27	Rupees Sixty Eight and Twenty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

27/07

27/07